

IMPROVEMENT PLANS FOR

HIGHLAND ESTATES - LOT 9 COBBLEHILL PLACE

COUNTY OF SAN MATEO, CALIFORNIA

255 SHORELINE DRIVE, SUITE 200
 REDWOOD CITY, CA 94065
 PHONE: (650) 482-6300
 FAX: (650) 482-6399

BKF
 ENGINEERS / SURVEYORS / PLANNERS

SHEET INDEX


SHEET NO	DESCRIPTION
C9.10	TITLE SHEET
C9.20	GENERAL NOTES, LEGEND AND ABBREVIATIONS
C9.30	SITE AND CLEARING, CONSTRUCTION AND GRADING PLANS
C9.40	UTILITY PLAN AND CROSS SECTION
C9.50	EROSION CONTROL PLANS
C9.60	EROSION CONTROL DETAILS AND NOTES
C9.70	CONSTRUCTION DETAILS
C9.71	CONSTRUCTION DETAILS
C9.80	LOGISTICS PLAN
C9.90	CASQA STANDARD DETAILS

EARTHWORK


CUT	140 CY
FILL	1800 CY
NET	1660 CY FILL

EARTHWORK NOTES:


- THE EARTHWORK QUANTITIES SHOWN ABOVE ARE IN-PLACE QUANTITIES AND HAVE BEEN ESTIMATED BY THE ENGINEER WITH THE FOLLOWING ASSUMPTIONS:
 - EARTHWORK QUANTITIES DO NOT ACCOUNT FOR SITE STRIPINGS.
 - THE UNIT PAD SECTION IS ASSUMED TO BE A 12" THICK CONCRETE SECTION.
 - EARTHWORK QUANTITIES DO NOT ACCOUNT FOR FILL SHRINKAGE FACTORS.
 - EARTHWORK QUANTITIES DO NOT ACCOUNT FOR UTILITY TRENCHING AND SPOILS.
 - EARTHWORK QUANTITIES DO NOT ACCOUNT FOR SOIL STABILIZATION FACTORS AND LANDSCAPING PLANTING SOILS.
 - EARTHWORK QUANTITIES DO NOT ACCOUNT FOR RETAINING WALLS AND BUILDING FOOTINGS AND BACKFILL.
- ACTUAL QUANTITIES MAY VARY DUE TO FIELD CONDITIONS OR CONSTRUCTION TECHNIQUES. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL QUANTITIES BASED UPON APPROVED PLANS AND INDEPENDENT CALCULATIONS.



VICINITY MAP
NTS



LOCATION MAP
NTS



SITE PLAN
SCALE: 1" = 50'

PROJECT DATA

SITE AREA:	17,997 SF
EXISTING LAND USE:	UNDEVELOPED LAND
PROPOSED USE:	RESIDENTIAL (LOT 9)
EXISTING ZONE:	RMD - RESOURCE MANAGEMENT DISTRICT
PROPOSED ZONE:	R-1
PROPOSED USE:	1 RESIDENTIAL LOT
OWNER:	TICONDEROGA PARTNERS, A CALIFORNIA LIMITED LIABILITY CORPORATION C/O THE CHAMBERLAIN GROUP 655 SKYWAY, SUITE 230 SAN CARLOS, CA 94070 (650) 595-5582 ATTN: JACK CHAMBERLAIN
DEVELOPER:	THE CHAMBERLAIN GROUP 655 SKYWAY, SUITE 230 SAN CARLOS, CA 94070 (650) 595-5582 ATTN: JACK CHAMBERLAIN
CIVIL ENGINEER:	BKF ENGINEERS 255 SHORELINE DRIVE, SUITE 200 REDWOOD CITY, CA 94065 (650) 482-6300
GEOTECHNICAL ENGINEER:	CORNERSTONE EARTH GROUP 1259 OAKMEAD PARKWAY SUNNYVALE, CA 94085 (408) 245-4600
WATER SUPPLY:	GAL WATER SERVICE 341 N. DELAWARE STREET SAN MATEO, CA 94401-1808 (650) 343-1808
SEWAGE DISPOSAL:	CITY OF SAN MATEO & CRYSTAL SPRINGS COUNTY SANITATION DISTRICT
GAS & ELECTRIC	PG&E
TELEPHONE:	AT&T
FIRE PROTECTION:	CALIFORNIA DEPARTMENT OF FORESTRY AND FIRE PROTECTION
CABLE:	COMCAST
STORM DRAINAGE:	COUNTY OF SAN MATEO CITY OF SAN MATEO
TOPOGRAPHIC BASE MAP:	AERO-GEOIDIC COROP. JOB NO. 950168 DATE OF PHOTOGRAPHY 9/18/87
EROSION CONTROL POINT OF CONTACT:	NOEL CHAMBERLAIN, NEXGEN BUILDERS INC. 225 DEMETER STREET EAST PALO ALTO, CA 94303 PHONE #: (650) 322-5800 CELL #: (650) 444-3089 EMAIL: noel@nexgenbuilders.com

ENGINEER'S STATEMENT

THESE IMPROVEMENT PLANS HAVE BEEN PREPARED BY ME OR UNDER MY DIRECTION IN ACCORDANCE WITH STANDARD ENGINEERING PRACTICE.

ROLAND N.V. HAGA
 R.C.E. NO. 43971
 BKF ENGINEERS

DATE




HIGHLAND ESTATES
 LOT 9 IMPROVEMENT PLANS
 TITLE SHEET
 SAN MATEO COUNTY
 CITY OF SAN MATEO
 CALIFORNIA

DRAWING NAME: K:\E:\095\950168\dwg\CD\Lot_9\C9_10-HECDTS.dwg
 PLOT DATE: 11-29-16
 PLOTTED BY: trat

No.	Revisions

Date: 11/29/2016
 Scale: NTS
 Design: JT
 Drawn: MD
 Approved: RH
 Job No: 950168-20
 Sheet Number:
C9.10
 OF


DRAWING NAME: K:\Projects\950168.dwg\CD\Lot_9\AC9_30-HECDSP.dwg
 PLOT DATE: 12-02-16 PLOTTED BY: tong



**LOT 9
 SITE PLAN**
 SCALE: 1"=10'



**LOT 9
 CLEARING, CONSTRUCTION, AND GRADING PLAN**
 SCALE: 1"=10'




**HIGHLAND ESTATES
 LOT 9 IMPROVEMENT PLANS
 SITE & CLEARING, CONSTRUCTION AND GRADING PLANS**
 CITY OF SAN MATEO SAN MATEO COUNTY CALIFORNIA

Revisions	No.	Date	By	Checked
Scale AS SHOWN	JT	11/29/2016		
Design	LF			
Drawn	RH			
Approved				
Job No.	950168-20			


HIGHLAND ESTATES
 LOT 9 IMPROVEMENT PLANS
 UTILITY PLAN AND CROSS SECTION
 CITY OF SAN MATEO SAN MATEO COUNTY

Revisions	No.	Date	Scale	AS SHOWN	Design	Drawn	Approved	Job No.
		11/29/2016			JT	LF	RH	950168-20

Sheet Number:
C9.40
 OF



**LOT 9
 UTILITY PLAN**
 SCALE: 1"=10'




**LOT 9
 CROSS SECTION A-A**
 SCALE: 1"=10'


NOTES:

- PER THE GEOTECHNICAL REPORT, UNDOCUMENTED FILL WAS MAPPED AT LOT 9 AND IF THIS FILL IS TO BE LEFT IN PLACE DURING HOUSE AND DRIVEWAY GRADING, IT SHOULD BE REPLACED AND REPLACED AS PROPERLY COMPACTED ENGINEERED FILL.
- PER THE GEOTECHNICAL REPORT, ALL EXISTING FILLS SHOULD BE COMPLETELY REMOVED FROM WITHIN PROPOSED HOUSE FOOTPRINT AND DRIVEWAY AREAS AND TO A LATERAL DISTANCE OF AT LEAST 2 FEET BEYOND THE EDGE OF THE IMPROVEMENTS. ANY EXCESS MATERIAL SHALL BE DISPOSED OF OFF-SITE IN A LAWFUL MANNER.
- PER THE GEOTECHNICAL REPORT, ALL BUILDING AND RETAINING WALLS SHOULD BE SUPPORTED ON DRILLED PIERS. THE FOUNDATION SHOWN ON THIS PLAN ARE SCHEMATIC. REFER TO THE PROJECT STRUCTURAL PLANS FOR DETAILS ON THE DRILLED PIERS.


DRAWING NAME: K:\E\950168\dwg\CD\Lot_9\C9_40-HECDSP.dwg
 PLOT DATE: 12-02-16
 PLOTTED BY: tong



Revisions	No.	Date	By
Scale	AS SHOWN	11/29/2016	JT
Design			LF
Drawn			LF
Approved			RH
Job No.	950168-20		



LOT 9
GRADING AND RETAINING WALL EROSION CONTROL PLAN
SCALE: 1"=10'



LOT 9
FOUNDATION AND CONSTRUCTION EROSION CONTROL PLAN
SCALE: 1"=10'

DRAWING NAME: K:\Eagles\950168\dwg\CD\Lot_9\C9_50-HECDSP.dwg
PLOT DATE: 12-02-16 PLOTTED BY: Long

Date	Scale	AS SHOWN	Drawn	Approved	Job No.
11/29/2016	AS SHOWN	JT	LF	RH	95088-20

Revisions


No.	Description

Sheet Number: **C9.60**





EROSION CONTROL NOTES

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
- ALTHOUGH SPECIFIC LOCATIONS FOR SEDIMENT CONTROL FACILITIES ARE SHOWN ON THESE PLANS, IT IS INTENDED THIS EROSION CONTROL PLAN BE MODIFIED WHEN NECESSARY TO MEET FIELD CONDITIONS. BASIN AND TRAP SIZES AND ELEVATIONS MAY BE ADJUSTED AS LONG AS THE MINIMUM AREAS AND DEPTHS FOR SEDIMENT SETTLING AND STORAGE ARE NOT REDUCED.
- THE INTENT OF THESE PLANS IS TO PROVIDE THE INITIAL CONCEPT FOR INTERIM EROSION CONTROL. THE CONTRACTOR SHALL UPDATE THE PLANS TO REFLECT CHANGING SITE CONDITIONS. PLAN UPDATES SHALL BE BASED UPON GENERAL SURVEY DATA. EROSION CONTROL EFFECTIVENESS SHALL ALSO BE MONITORED AND THE PLANS UPGRADED AS REQUIRED TO PREVENT SIGNIFICANT QUANTITIES OF SEDIMENT FROM ENTERING THE DOWNSTREAM DRAINAGE SYSTEM.
- THIS PLAN MAY NOT COVER ALL THE SITUATIONS THAT ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. IN GENERAL, THE CONTRACTOR IS RESPONSIBLE FOR KEEPING THE STORM RUN OFF FROM LEAVING THE SITE. FIBER ROLLS, SAND BAGS, AND SILT FENCES SHALL BE USED BY THE CONTRACTOR ON AN AS NEEDED BASIS TO INHIBIT SILT FROM LEAVING THE SITE AND ENTERING THE STORM DRAIN SYSTEM. ALL EXISTING, TEMPORARY, OR PERMANENT CATCH BASINS SHALL USE ONE OF THE SEDIMENT BARRIERS SHOWN.
- THE CONTRACTOR WILL BE LIABLE FOR ANY AND ALL DAMAGES TO PUBLIC AND/OR PRIVATE OWNED AND MAINTAINED ROAD CAUSED BY THE CONTRACTOR'S GRADING ACTIVITIES, AND WILL BE RESPONSIBLE FOR THE CLEANUP OF ANY MATERIAL SPILLED ON ANY PUBLIC ROAD ON THE HAUL ROUTE. ADJACENT PUBLIC ROADS SHALL BE CLEANED AT THE END OF EACH WORKING DAY.
- BEST MANAGEMENT PRACTICES SHALL BE OPERABLE YEAR AROUND.
- DURING THE RAINY SEASON, ALL PAVED AREAS ARE TO BE KEPT CLEAR OF EARTH MATERIAL AND DEBRIS. THE SITE IS TO BE MAINTAINED SO AS TO MINIMIZE SEDIMENT-LADEN RUNOFF TO ANY STORM DRAIN SYSTEM.
- ALL EROSION CONTROL FACILITIES MUST BE INSPECTED AND REPAIRED DAILY DURING THE RAINY SEASON. ALL SLOPES SHALL BE REPAIRED AS SOON AS POSSIBLE WHEN DAMAGED.
- THE FIRST PHASE OF CONSTRUCTION SHALL REQUIRE 30 PERCENT OF CONSTRUCTION EQUIPMENT TO MEET TIER 1 EPA CERTIFICATION STANDARDS FOR CLEAN TECHNOLOGY. THE REMAINDER OF CONSTRUCTION EQUIPMENT (70 PERCENT), WHICH WOULD CONSIST OF OLDER TECHNOLOGIES, SHALL BE REQUIRED TO USE EMULSIFIED FUELS.
- THE SECOND PHASE OF CONSTRUCTION SHALL REQUIRE 30 PERCENT OF CONSTRUCTION EQUIPMENT TO MEET TIER 2 EPA CERTIFICATION STANDARDS FOR CLEAN TECHNOLOGY AND 50 PERCENT TO MEET TIER 1 EPA CERTIFICATION STANDARDS. THE REMAINING 20 PERCENT OF CONSTRUCTION EQUIPMENT, WHICH WOULD CONSIST OF OLDER TECHNOLOGIES, SHALL USE EMULSIFIED FUELS.
- FOR ALL LARGER VEHICLES, INCLUDING CEMENT MIXERS OR OTHER DEVICES THAT MUST BE DELIVERED BY LARGE TRUCKS, VEHICLES SHALL BE EQUIPPED WITH CAB LEVEL THREE VERIFIED CONTROL DEVICES.
- WATER ALL ACTIVE CONSTRUCTION AREAS AT LEAST TWICE DAILY.
- COVER ALL TRUCKS HAULING SOIL, SAND, AND OTHER LOOSE MATERIALS OR REQUIRE ALL TRUCKS TO MAINTAIN AT LEAST TWO FEET OF FREEBOARD.
- PAVE, APPLY WATER THREE TIMES DAILY, OR APPLY NON-TOXIC SOIL STABILIZERS ON ALL UNPAVED ACCESS ROADS, PARKING AREAS, AND STAGING AREAS AT THE CONSTRUCTION SITES.
- SWEEP DAILY (WITH WATER SWEEPERS) ALL PAVED ACCESS ROADS, PARKING AREAS, AND STAGING AREAS AT THE CONSTRUCTION SITES.
- SWEEP PUBLIC STREETS ADJACENT TO CONSTRUCTION SITES DAILY (WITH WATER SWEEPERS) IF VISIBLE SOIL MATERIAL IS CARRIED ONTO THE STREETS.
- HYDROSEED OR APPLY NON-TOXIC SOIL STABILIZERS TO INACTIVE CONSTRUCTION AREAS (PREVIOUSLY GRADED AREAS INACTIVE FOR TEN DAYS OR MORE).
- TEMPORARY AND PERMANENT SLOPES GREATER THAN 3 FEET SHALL BE SEEDED UNLESS ALTERNATIVE MEASURES ARE USED.
- SEED MIX FOR REVEGETATION AND HYDROSEEDING:
NORTHERN CALIFORNIA COVER MIX BY ACBRIGHT OR EQUAL
30% BLUE MILDREY
30% MEADOW BARLEY
20% ZORRO FESCUE
10% PURPLE NEEDLE GRASS
10% CALIFORNIA NATIVE WILDFLOWERS
APPLY AT 40 POUNDS PER ACRE MINIMUM
- ENCLOSE, COVER, WATER TWICE DAILY, OR APPLY NON-TOXIC SOIL BINDERS TO EXPOSED STOCKPILES (DIRT, SAND, ETC.). LIMIT TRAFFIC SPEEDS ON UNPAVED ROADS TO 15 MILES PER HOUR.
- DISPOSAL AREAS FOR SEDIMENT TO BE DETERMINED IN FIELD. WHEN MATERIAL IS STOCKPILED, IT SHALL BE SURROUNDED BY A SILT FENCE/FIBER ROLLS.
- LIMIT TRAFFIC SPEEDS ON UNPAVED ROADS TO 15 MILES PER HOUR.
- INSTALL SANDBAGS OR OTHER EROSION CONTROL MEASURES TO PREVENT SILT RUNOFF TO PUBLIC ROADWAYS.
- REPLANT VEGETATION IN DISTURBED AREAS AS SOON AS POSSIBLE.
- INSTALL WHEEL WASHERS FOR ALL EXITING TRUCKS OR WASH OFF THE TIRES OR TRACKS OF ALL TRUCKS AND EQUIPMENT LEAVING THE CONSTRUCTION SITE.
- INSTALL WIND BREAKS AT THE WINDWARD SIDES OF THE CONSTRUCTION AREAS.
- SUSPEND EXCAVATION AND GRADING ACTIVITIES WHEN WIND (AS INSTANTANEOUS GUSTS) EXCEEDS 25 MILES PER HOUR.
- NO GRADING SHALL BE ALLOWED DURING THE WINTER SEASON (OCTOBER 15 TO APRIL 30) TO AVOID POTENTIAL SOIL EROSION UNLESS APPROVED, IN WRITING, BY THE COMMUNITY DEVELOPMENT DIRECTOR. THE PROPERTY OWNERS SHALL SUBMIT A LETTER TO THE CURRENT PLANNING SECTION, AT LEAST TWO WEEKS PRIOR TO COMMENCEMENT OF GRADING, STATING THE DATE WHEN GRADING WILL BEGIN.
- STABILIZE ALL DENUDED AREAS AND MAINTAIN EROSION CONTROL MEASURES CONTINUOUSLY BETWEEN OCTOBER 15 AND APRIL 30. STABILIZING SHALL INCLUDE BOTH PROACTIVE MEASURES, SUCH AS THE PLACEMENT OF STRAW BALES OR COIR NETTING, AND PASSIVE MEASURES, SUCH AS MINIMIZING VEGETATION REMOVAL AND REVEGETATING DISTURBED AREAS WITH VEGETATION THAT IS COMPATIBLE WITH THE SURROUNDING ENVIRONMENT.
- STORE, HANDLE, AND DISPOSE OF CONSTRUCTION MATERIALS AND WASTES PROPERLY, SO AS TO PREVENT THEIR CONTACT WITH STORMWATER.


- CONTROL AND PREVENT THE DISCHARGE OF ALL POTENTIAL POLLUTANTS, INCLUDING PAVEMENT CUTTING WASTES, PAINTS, CONCRETE, PETROLEUM PRODUCTS, CHEMICALS, WASH WATER OR SEDIMENTS, AND NON-STORMWATER DISCHARGES TO STORM DRAINS AND WATERCOURSES.
- USE SEDIMENT CONTROLS OR FILTRATION TO REMOVE SEDIMENT WHEN DEWATERING SITE AND OBTAINING ALL NECESSARY PERMITS.
- AVOID CLEANING, FUELING, OR MAINTAINING VEHICLES ON-SITE, EXCEPT IN A DESIGNATED AREA WHERE WASH WATER IS CONTAINED AND TREATED.
- DELINEATE WITH FIELD MARKERS CLEARING LIMITS, SETBACKS, AND DRAINAGE COURSES.
- PROTECT ADJACENT PROPERTIES AND UNDISTURBED AREAS FROM CONSTRUCTION IMPACTS USING VEGETATIVE BUFFER STRIPS, SEDIMENT BARRIERS OR FILTERS, DIKES, MULCHING, OR OTHER MEASURES AS APPROPRIATE.
- PERFORM CLEARING AND EARTH-MOVING ACTIVITIES ONLY DURING DRY WEATHER.
- LIMIT AND TIME APPLICATIONS OF PESTICIDES AND FERTILIZERS TO PREVENT POLLUTED RUNOFF.
- LIMIT CONSTRUCTION ACCESS ROUTES AND STABILIZE DESIGNATED ACCESS POINTS.
- ALL GRADED SURFACES AND MATERIALS, WHETHER FILLED, EXCAVATED, TRANSPORTED OR STOCKPILED, SHALL BE WETTED, PROTECTED OR CONTAINED IN SUCH A MANNER AS TO PREVENT ANY SIGNIFICANT NUISANCE FROM DUST, OR SPILLAGE UPON ADJOINING WATER BODY, PROPERTY, OR STREETS. EQUIPMENT AND MATERIALS ON THE SITE SHALL BE USED IN SUCH A MANNER AS TO AVOID EXCESSIVE DUST. A DUST CONTROL PLAN MAY BE REQUIRED AT ANYTIME DURING THE COURSE OF THE PROJECT.
- A DUST PALLIATIVE SHALL BE APPLIED TO THE SITE WHEN REQUIRED BY THE COUNTY. THE TYPE AND RATE OF APPLICATION SHALL BE RECOMMENDED BY THE SOILS ENGINEER AND APPROVED BY THE DEPARTMENT OF PUBLIC WORKS, THE PLANNING AND BUILDING DEPARTMENT'S GEOTECHNICAL SECTION, AND THE REGIONAL WATER QUALITY CONTROL BOARD.
- IF NO WORK HAS PROCEEDED FOR A PERIOD OF 6-WEEKS, FINAL DRAINAGE AND EROSION CONTROL IMPROVEMENTS SHALL BE INSTALLED IN ACCORDANCE WITH AN APPROVED WINTERIZATION PLAN.
- PADS SHALL BE GRADED TO MINIMIZE STANDING WATER. SPECIFIC LOCATIONS REQUIRING SUPPLEMENTAL GRADING TO ACHIEVE ACCEPTABLE DRAINAGE SHALL BE DETERMINED BY THE CONSTRUCTION MANAGER. ALL SPOILS AND SOIL STOCKPILES REMAINING ON SITE SHALL BE ENCLOSED BY SILT FENCES/FIBER ROLLS.
- STUBBED OUT ENDS OF PARTIALLY COMPLETED SUBDRAINS SHALL BE WRAPPED WITH AN APPROVED FABRIC TO PREVENT SOIL AND DEBRIS FROM ENTERING THE PIPE.
- HAUL ROADS ARE CURRENTLY NOT SHOWN ON THE PLANS. EROSION CONTROL MEASURES SHALL BE TAKEN TO MINIMIZE EROSION RELATED TO HAUL ROADS.
- GRADING SCHEDULE SHALL BE SUBMITTED FOR APPROVAL TO SAN MATEO COUNTY PUBLIC WORKS BY AUGUST 15.
- EROSION CONTROL POINT OF CONTACT:
NOEL CHAMBERLAIN, NEXGEN BUILDERS INC.
225 DEMETER STREET
EAST PALO ALTO, CA 94303
PHONE #: 650-322-5800
CELL #: 650-444-3099
EMAIL: noel@nexgenbuilders.com
- SHOULD IT APPEAR THAT THE EROSION CONTROL PLAN, OR ANY OTHER MATTER THERETO, IS NOT SUFFICIENTLY DETAILED OR EXPLAINED ON THESE PLANS, THE CONTRACTOR SHALL CONTACT THE BKF PROJECT ENGINEER AT (650) 482-6300 FOR SUCH FURTHER EXPLANATIONS AS MAY BE NECESSARY.
- AREAS DELINEATED ON PLANS FOR PARKING, CLEARING & GRUBBING, STORAGE, ETC. SHALL NOT BE ENLARGED OR "RUN OVER."
- CONSTRUCTION SITES ARE REQUIRED TO HAVE EROSION CONTROL MATERIALS ON-SITE DURING THE "OFF-SEASON."
- DUST CONTROL IS REQUIRED YEAR-ROUND.
- EROSION CONTROL MATERIALS SHALL BE STORED ON-SITE.
- USE OF PLASTIC SHEETING BETWEEN OCTOBER 1ST AND APRIL 30TH IS NOT ACCEPTABLE, UNLESS FOR USE ON STOCKPILES WHERE THE STOCKPILE IS ALSO PROTECTED WITH FIBER ROLLS CONTAINING THE BASE OF THE STOCKPILE.
- TREE PROTECTION SHALL BE IN PLACE BEFORE ANY GRADING, EXCAVATING OR GRUBBING IS STARTED.



- NOTES:
- ALL CONSTRUCTION ENTRANCES SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND, AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USE TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PUBLIC RIGHT-OF-WAYS SHALL BE REMOVED IMMEDIATELY.
 - WHEELS SHALL BE CLEAN PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAYS. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE THROUGH USE OF INLET PROTECTION (E.G. SAND BAGS OR OTHER APPROVED METHODS).
 - THE MATERIAL FOR CONSTRUCTION OF THE PAD SHALL BE 4" TO 6" STONE.
 - THE THICKNESS OF THE PAD SHALL NOT BE LESS THAN 12".
 - THE WIDTH OF THE PAD SHALL NOT BE LESS THAN THE FULL WIDTH OF ALL POINTS OF INGRESS OR EGRESS.
 - THE LENGTH OF THE PAD SHALL NOT BE LESS THAN 50'.



- NOTES:
- PLACE FIBER ROLLS AROUND THE INLET CONSISTENT WITH BASIN SEDIMENT BARRIER DETAIL ON THIS SHEET. (FIBER ROLLS ARE TUBES MADE FROM STRAW BOUND W/ PLASTIC NETTING. THEY ARE APPROX. 8" DIA. AND 20 - 30 FT. LONG.)
 - FIBER ROLL INSTALLATION REQUIRES THE PLACEMENT AND SECURE STAKING OF THE FIBER ROLL IN A TRENCH, 3" - 4" DEEP, DUG ON CONTOUR. RUNOFF MUST NOT BE ALLOWED TO RUN UNDER OR AROUND FIBER ROLL.
 - THE TOP OF THE STRUCTURE (PONDING HEIGHT) MUST BE WELL BELOW THE GROUND ELEVATION DOWNSLOPE TO PREVENT RUNOFF FROM BY-PASSING THE INLET. EXCAVATION OF A BASIN ADJACENT TO THE DROP INLET OR A TEMPORARY DIKE ON THE DOWNSLOPE OF THE STRUCTURE MAY BE NECESSARY.




- NOTES:
- THE APPLICANT SHALL ESTABLISH AND MAINTAIN TREE PROTECTION ZONES THROUGHOUT THE ENTIRE LENGTH OF THE PROJECT.
 - TREE PROTECTION ZONES SHALL BE DELINEATED USING 4-FOOT TALL ORANGE PLASTIC FENCING SUPPORTED BY POLES POUNDED INTO THE GROUND, LOCATED AS CLOSE TO THE DRIPLINES AS POSSIBLE WHILE STILL ALLOWING ROOM FOR CONSTRUCTION/GRADING TO SAFELY CONTINUE.
 - THE APPLICANT SHALL MAINTAIN TREE PROTECTION ZONES FREE OF EQUIPMENT AND MATERIALS STORAGE AND SHALL NOT CLEAN ANY EQUIPMENT WITHIN THESE AREAS.
 - SHOULD ANY LARGE ROOTS OR LARGE MASSES OF ROOTS NEED TO BE CUT, THE ROOTS SHALL BE INSPECTED BY A CERTIFIED ARBORIST OR REGISTERED FORESTER PRIOR TO CUTTING. ANY ROOT CUTTING SHALL BE MONITORED BY AN ARBORIST OR FORESTER AND DOCUMENTED.
 - ROOTS TO BE CUT SHOULD BE SEVERED CLEANLY WITH A SAW OR TOPPERS.
 - NORMAL IRRIGATION SHALL BE MAINTAINED, BUT OAKS SHOULD NOT NEED SUMMER IRRIGATION.
 - THE ABOVE INFORMATION SHALL BE ON-SITE AT ALL TIMES.

CALIFORNIA STORMWATER QUALITY ASSOCIATION (CASQA) STANDARD DETAIL REFERENCES


(CALIFORNIA STORMWATER BMP HANDBOOK CONSTRUCTION, DATED NOVEMBER 2009)
NOTE: ALTHOUGH SPECIFIC LOCATIONS FOR SPECIFIC BMPs ARE SHOWN ON THESE PLANS, IT IS INTENDED FOR THE CONTRACTOR TO APPLY APPROPRIATE BMPs WHEN NECESSARY TO MEET FIELD CONDITIONS.

EROSION CONTROL BMPs:	TEMPORARY TRACKING CONTROL BMPs:
EC-1 SCHEDULING	TC-1 STABILIZED CONSTRUCTION ENTRANCE/EXIT
EC-2 PRESERVATION OF EXISTING VEGETATION	TC-2 STABILIZED CONSTRUCTION ROADWAY
EC-3 HYDRAULIC MULCH	TC-3 ENTRANCE/OUTLET TIRE WASH
EC-4 HYDROSEEDING	
EC-5 SOIL BINDERS	NON-STORMWATER MANAGEMENT BMPs:
EC-6 STRAW MULCH	NS-1 WATER CONSERVATION PRACTICES
EC-7 GEOTEXTILES & MATS	NS-2 DEWATERING OPERATIONS
EC-8 WOOD MULCHING	NS-3 PAVING AND GRINDING OPERATIONS
EC-9 EARTH DIKES AND DRAINAGE SWALES	NS-4 TEMPORARY STREAM CROSSING
EC-10 VELOCITY DISSIPATION DEVICES	NS-5 CLEAR WATER DIVERSION
EC-11 SLOPE DRAINS	NS-6 ILLICIT CONNECTION/DISCHARGE
EC-12 STREAMBANK STABILIZATION	NS-7 POTABLE WATER/IRRIGATION
EC-14 COMPOST BLANKETS	NS-8 VEHICLE AND EQUIPMENT CLEANING
EC-15 SOIL PREPARATION/ROUGHENING	NS-9 VEHICLE AND EQUIPMENT FUELING
EC-16 NON-VEGETATIVE STABILIZATION	NS-10 VEHICLE AND EQUIPMENT MAINTENANCE
	NS-11 PILE DRIVING OPERATIONS
TEMPORARY SEDIMENT CONTROL BMPs:	NS-12 CONCRETE CURING
SE-1 SILT FENCE	NS-13 CONCRETE FINISHING
SE-2 SEDIMENT BASIN	NS-14 MATERIAL AND EQUIPMENT USE
SE-3 SEDIMENT TRAP	NS-15 DEMOLITION ADJACENT TO WATER
SE-4 CHECK DAM	NS-16 TEMPORARY BATCH PLANTS
SE-5 FIBER ROLLS	
SE-6 GRAVEL BAG BERM	WASTE MANAGEMENT & MATERIALS POLLUTION CONTROL BMPs:
SE-7 STREET SWEEPING AND VACUUMING	WM-1 MATERIAL DELIVERY AND STORAGE
SE-8 SANDBAG BARRIER	WM-2 MATERIAL USE
SE-9 STRAW BALE BARRIER	WM-3 STOCKPILE MANAGEMENT
SE-10 STORM DRAIN INLET PROTECTION	WM-4 SPILL PREVENTION AND CONTROL
SE-11 ACTIVE TREATMENT SYSTEMS	WM-5 SOLID WASTE MANAGEMENT
SE-12 TEMPORARY SILT DIKE	WM-6 HAZARDOUS WASTE MANAGEMENT
SE-13 COMPOST SOCKS AND BERMS	WM-7 CONTAMINATED SOIL MANAGEMENT
SE-14 BIOFILTER BAGS	WM-8 CONCRETE WASTE MANAGEMENT
	WM-9 SANITARY/SEPTIC WASTE MANAGEMENT
WIND EROSION CONTROL BMPs:	WM-10 LIQUID WASTE MANAGEMENT
WE-1 WIND EROSION CONTROL	


No.	Date	Revisions
	11/29/2016	Scale AS SHOWN
		Design JT
		Drawn LF
		Approved RH
		Job No. 950168-20




6 SAN MATEO COUNTY OVERFLOW AND BACKFLOW DEVICE DETAIL
NTS




5 SAN MATEO COUNTY DRIVEWAY PLAN AND PROFILE VIEWS
NTS




4 SAN MATEO COUNTY TYPICAL SEWER CLEANOUT & BOX DETAIL
NTS



3 SAN MATEO COUNTY CURB CUT
NTS




2 SAN MATEO COUNTY CLEANOUT
NTS



1 SAN MATEO COUNTY FLOW-THROUGH PLANTER (FTP)
NTS

DRAWING NAME: K:\E:\950168\dwg\CD\Lot_9\AC9_70-HECDDT.dwg
PLOT DATE: 11-29-16
PLOTTED BY: tral





NOTES

- SAND... MATERIAL FREE FROM ORGANIC MATTER AND CLAY WITH A SIEVE GRADATION BY WEIGHT AS FOLLOWS:



SIEVE SIZE	% PASSING SIEVE
No. 4	100
No. 200	0-5
- STRUCTURE BACKFILL MATERIAL... MATERIAL WITH SAND EQUIVALENT NOT LESS THAN 20 AND SIEVE GRADATION BY WEIGHT AS FOLLOWS:

SIEVE SIZE	% PASSING SIEVE
3"	100
No. 4	35-100
No. 30	20-100
- BACKFILL MATERIAL... MATERIAL FROM EXCAVATION, FREE FROM STONES OR LUMPS EXCEEDING 3 INCHES GREATEST DIMENSION, ORGANIC MATTER, OR OTHER UNSATISFACTORY MATERIAL.



NOTES:

- AREA OF ROCK RIP-RAP OUTFALL/EROSION PROTECTION IN ACCORDANCE WITH FEDERAL HIGHWAY ADMINISTRATION (FHWA) HEC-14.
- OUTFALL PROTECTION MATERIAL:
 - CALTRANS ROCK SLOPE PROTECTION FABRIC WITH NO. 2 BACKING CONFORMING TO SECTION 72 OF THE CALTRANS STANDARD SPECIFICATIONS.
 - CALTRANS NO. 2 TO BE ~8" SIZE ANGULAR ROCK (25 LBS, TYP.) BROWN TO DARK BROWN/BLACK IN COLOR.





NOTES:

- ALL MATERIAL USED IN MANUFACTURING SHALL CONFORM TO A.S.T.M. A48, CLASS 30.
- ALL CASTINGS TO BE COMPLETELY CLEANED AND PAINTED WITH ASPHALTIC VARNISH, AFTER MANUFACTURE.
- USE PHOENIX P-1090, D&L SUPPLY A-1024, OR EQUAL.


2 MANHOLE FRAME AND COVER
 NTS

4 INLET PROTECTION
 NTS




NOTES:

- PRE-CAST MANHOLE MATERIAL SHALL BE MANUFACTURED TO ASTM SPECIFICATION C478.
- GROUT JOINTS WITH 1:3 MORTAR MIX OR USE RAM-NEK JOINT COMPOUND.
- A 30° TAPER MAY BE COMBINED WITH A 12° VERTICAL TO FORM A 48° TAPER SECTION.
- ALL CONCRETE JOINTS SHALL BE LEANED, WETTED, AND MORTARED PRIOR TO SETTING THE NEXT SECTION. THE JOINTS SHALL BE PACKED, TOWELLED AND BRUSHED WHILE THE MORTAR IS PLASTIC.
- MANHOLE SHALL BE SET TO GRADE SUBSEQUENT TO PLACING AC OR RCC.
- XYPEX CONCENTRATE/CRYSTALLINE COATING ON INTERIOR CONCRETE SURFACES.
- STEPS NOT REQUIRED IN MANHOLES 3.5 FEET OR LESS IN DEPTH.



6 STANDARD TRENCH BACKFILL & BEDDING DETAIL
 NTS



CENTRAL PRECAST


MODEL	A	B	C
CP1212	12	12	4
CP1818	18	18	4
CP2424	24	24	5

NOTES:

- DROP INLET SHALL BE CENTRAL PRECAST OR APPROVED EQUAL.
- AN ENGINEERED PRECAST DROP INLET UNIT CAN BE USED AS AN ALTERNATE.

DRAWING NAME: K:\E\950168\dwg\CD\Lot_9\AC_71-HECDDT.dwg
 PLOT DATE: 12-02-16
 PLOTTED BY: Long

No.	Date	By	Check	Appr.	Job No.
	11/29/2016	AS SHOWN	JT	LF	950168-20
		Design			
		Drawn			
		Approved			



CALIFORNIA

HIGHLAND ESTATES
LOT 9 IMPROVEMENT PLANS
LOGISTICS PLAN
SAN MATEO COUNTY
CITY OF SAN MATEO

Revisions	
No.	Date
	11/29/2016
	Scale 1"=20'
	Design JT
	Drawn LF
	Approved RH
	Job No. 950168-20

Sheet Number:
C9.80
OF




SITE KEY:

- ① WASH OUT PIT, PER CASQA STANDARD WM-8, CONCRETE WASTE MANAGEMENT (REFER TO DETAIL 2, SHEET C9.90).
- ② TOILETS AND HAND WASH STATION
- ③ MATERIALS STORAGE
- ④ DEBRIS BOX LOCATION
- ⑤ TOOL STORAGE LOCKER
- ⑥ JOB SITE TRAILER
- ⑦ STOCKPILE AREA
- ⑧ CONSTRUCTION EQUIPMENT PARKING



CONSTRUCTION NOTES:

- 1. CONSTRUCTION ACCESS ROUTE SHALL BE FROM COBBLEHILL PLACE TO INTERSTATE 280.
- 2. STOCKPILE TO CONFORM TO CASQA STANDARD WM-3, STOCKPILE MANAGEMENT (REFER TO DETAIL 1, SHEET C9.90).
- 3. CONSTRUCTION VEHICLE PARKING AREA SHALL HAVE 4"-6" AGGREGATE OVER GEO-TEXTILE FABRIC.



DRAWING NAME: K:\E\950168.dwg\CD\Lot_9\C9_80-HECDLP.dwg
PLOT DATE: 11-29-16 PLOTTED BY: trat

255 SHORELINE DRIVE, SUITE 200
REDWOOD CITY, CA 94065
PHONE: (650) 482-6300
FAX: (650) 482-6399



CALIFORNIA


HIGHLAND ESTATES
LOT 9 IMPROVEMENT PLANS
CASQA STANDARD DETAILS
SAN MATEO COUNTY
CITY OF SAN MATEO

Revisions	
No.	
Date	11/29/2016
Scale	AS SHOWN
Design	JT
Drawn	LF
Approved	RH
Job No.	950168-20

Sheet Number:
C9.90
OF

Stockpile Management

WM-3



Categories

EC	Erosion Control	
SE	Sediment Control	<input checked="" type="checkbox"/>
TC	Tracking Control	
WE	Wind Erosion Control	
NS	Non-Stormwater Management Control	<input checked="" type="checkbox"/>
WM	Waste Management and Materials Pollution Control	<input checked="" type="checkbox"/>

Legend:
 Primary Category
 Secondary Category

Description and Purpose
Stockpile management procedures and practices are designed to reduce or eliminate air and stormwater pollution from stockpiles of soil, soil amendments, sand, paving materials such as portland cement concrete (PCC) rubble, asphalt concrete (AC), asphalt concrete rubble, aggregate base, aggregate sub base or pre-mixed aggregate, asphalt binder (so called "cold mix" asphalt), and pressure treated wood.

Suitable Applications
Implement in all projects that stockpile soil and other loose materials.

- Limitations**
- Plastic sheeting as a stockpile protection is temporary and hard to manage in windy conditions. Where plastic is used, consider use of plastic tarps with nylon reinforcement which may be more durable than standard sheeting.
 - Plastic sheeting can increase runoff volume due to lack of infiltration and potentially cause perimeter control failure.
 - Plastic sheeting breaks down faster in sunlight.
 - The use of plastic materials should be avoided when feasible and photodegradable plastics should not be used.

Implementation
Protection of stockpiles is a year-round requirement. To properly manage stockpiles:

Targeted Constituents

Sediment	<input checked="" type="checkbox"/>
Nutrients	<input checked="" type="checkbox"/>
Trash	<input checked="" type="checkbox"/>
Metals	<input checked="" type="checkbox"/>
Bacteria	<input checked="" type="checkbox"/>
Oil and Grease	<input checked="" type="checkbox"/>
Organics	<input checked="" type="checkbox"/>

Potential Alternatives
none



January 2011
Construction
www.casqa.org

Stockpile Management

WM-3

- On larger sites, a minimum of 50 ft separation from concentrated flows of stormwater, drainage courses, and inlets is recommended.
- All stockpiles are required to be protected immediately if they are not scheduled to be used within 14 days.
- Protect all stockpiles from stormwater run-on using temporary perimeter sediment barriers such as compost berms (SE-13), temporary silt dikes (SE-12), fiber rolls (SE-5), silt fences (SE-1), sandbags (SE-8), gravel bags (SE-6), or biofilter bags (SE-14). Refer to the individual fact sheet for each of these controls for installation information.
- Implement wind erosion control practices as appropriate on all stockpiled material. For specific information, see WE-1, Wind Erosion Control.
- Manage stockpiles of contaminated soil in accordance with WM-7, Contaminated Soil Management.
- Place bagged materials on pallets and under cover.
- Ensure that stockpile coverings are installed securely to protect from wind and rain.
- Some plastic covers withstand weather and sunlight better than others. Select cover materials or methods based on anticipated duration of use.

Protection of Non-Active Stockpiles
Non-active stockpiles of the identified materials should be protected further as follows:

- Soil stockpiles**
- Cover and protect soil stockpiles with soil stabilization measures and a temporary perimeter sediment barrier at all times.
 - Consider temporary vegetation for topsoil piles that will be stockpiled for extended periods.
- Stockpiles of Portland cement concrete rubble, asphalt concrete, asphalt concrete rubble, aggregate base, or aggregate sub base**
- Provide covers and protect these stockpiles with a temporary perimeter sediment barrier at all times.
- Stockpiles of "cold mix"**
- Cover cold mix stockpiles and place them on plastic sheeting (or comparable material) and surround the stockpiles with a berm all times.
- Stockpiles of fly ash, stucco, hydrated lime**
- Cover stockpiles of materials that may raise the pH of runoff (i.e., basic materials) with plastic and surround the stockpiles with a berm at all times.

January 2011
Construction
www.casqa.org

WM-3 - STOCKPILE MANAGEMENT

NTS

Stockpile Management

WM-3

Stockpiles/Storage of wood (Pressure treated with chromated copper arsenate or ammoniacal copper zinc arsenate)

- Cover treated wood with plastic sheeting (or comparable material) and surround with a berm at all times.

Protection of Active Stockpiles
Active stockpiles of the identified materials should be protected as follows:


- All stockpiles should be covered and protected with a temporary linear sediment barrier prior to the onset of precipitation.
- Stockpiles of "cold mix" and treated wood, and basic materials should be placed on and covered with plastic sheeting or comparable material and surrounded by a berm prior to the onset of precipitation.
- The downstream perimeter of an active stockpile should be protected with a linear sediment barrier or berm and runoff should be diverted around or away from the stockpile on the upstream perimeter.

Costs
For cost information associated with stockpile protection refer to the individual erosion or sediment control BMP fact sheet considered for implementation (For example, refer to SE-1 Silt Fence for installation of silt fence around the perimeter of a stockpile.)

- Inspection and Maintenance**
- Stockpiles must be inspected in accordance with General Permit requirements for the associated project type and risk level. It is recommended that at a minimum, BMPs be inspected weekly, prior to forecasted rain events, daily during extended rain events, and after the conclusion of rain events.
 - It may be necessary to inspect stockpiles covered with plastic sheeting more frequently during certain conditions (for example, high winds or extreme heat).
 - Repair and/or replace perimeter controls and covers as needed to keep them functioning properly.
 - Sediment shall be removed when it reaches one-third of the barrier height.

References
Stormwater Quality Handbooks - Construction Site Best Management Practices (BMPs) Manual, State of California Department of Transportation (Caltrans), March 2003.



January 2011
Construction
www.casqa.org



1
STOCKPILE COVERING
(PER CASQA STANDARD WM-3, STOCKPILE MANAGEMENT, SEE LEFT) NTS

Concrete Waste Management



WM-8



November 2009
California Stormwater BMP Handbook
Construction
www.casqa.org
6 of 7

Concrete Waste Management


WM-8



November 2009
California Stormwater BMP Handbook
Construction
www.casqa.org
7 of 7

WM-8 - CONCRETE WASTE MANAGEMENT

NTS



2
TEMPORARY WASHOUT PIT
(PER CASQA STANDARD WM-8, CONCRETE WASTE MANAGEMENT, SEE LEFT) NTS

DRAWING NAME: K:\E:\95\950168\dwg\CD\Lot_9\C9_90-HEDEC.dwg
PLOT DATE: 11-29-16
PLOTTED BY: trat